

# Construction Waste Management Plan

## Fit out waste skip for on/offsite segregation

### Active Compactable/Non Compactable Waste

#### Lightweight

Paper and Cardboard  
Polythene shrink wrap  
Polystyrene or other material packaging  
Wood off cuts  
Plastic off cuts

#### Non Compactable

Damaged joinery units  
MDF chipboard  
Plastic pipe work



### Notes

1. Steel, copper wire and other metal work to be segregated on site for recycling in larger quantities
2. Waste electrical and electronic equipment (WEEE) will be disposed of in compliance with the WEEE directive (2nd January 2007)
3. Separate containers should be used for hazardous waste:
  - Fluorescent light tubes
  - Paint tins
  - Aerosol cans
  - Mastic tubes
  - Resins
  - Plasterboard



Get some space in your life.™